

# Validation and Uncertainty Characterization for Energy Simulation

Multi-Zone HVAC System using ORNL's Flexible Research Platform (FRP)

For: ASHRAE SSPC140


June 26, 2016

PM: Joshua New

PIs – Piljae Im and Mahabir Bhandari



## (DRAFT – Illustrative only)






# Flexible Research Platform

- HVAC System Performance Measurement, Modeling, Calibration and Validation

## Weather Station


## HVAC #1: RTU with VAV Reheating



## Sensors & Data Acquisition



## Simulated Occupancy



# 2 Story FRP Characteristics w/ Baseline RTU VAV Reheat



Building component	Value
Location	Oak Ridge, Tennessee
Building width	40 ft
Building length	40 ft
Story height (floor to floor)	14 ft
Number of floors	2
Number of thermal zones	10 (8 perimeter and 2 core)
Wall structure	Concrete masonry unit (CMU) with face brick
Wall insulation	Fiberglass R-11
Floor	Slab on grade
Roof structure	Metal deck with polyiso and EPDM
Roof insulataion	Polyiso R-18
Windows	Double clear glazing
Window-to-wall ratio	28%
Lighting power density	0.85 W/ft <sup>2</sup>
Equipment power density	1.3 W/ft <sup>2</sup>
Baseline RTU capacity	12.5 ton
EER	9.7
Reheat	VAV box with electric reheat



# Occupancy Simulation

- Various sources to define the schedules & power density

- ASHRAE 90.1-1989
- Huang et al. (1990) 481 PROTOTYPICAL COMMERCIAL BUILDINGS FOR 20 URBAN MARKET AREAS, LBL-29798
- Huang and Franconi (1999) COMMERCIAL HEATING AND COOLING LOADS COMPONENT ANALYSIS
- PNNL report (1990) ARCHITECT'S AND ENGINEER'S GUIDE TO ENERGY CONSERVATION IN EXISTING BUILDINGS: Volume 1 - Energy Use Assessment and Simulation Methods



# Add latent, sensible, and lighting load to space according to occupancy schedule

## Internal Heat Loads


Sensible:  
from  
occupants  
and MELs



Latent: from  
occupants




Lighting



## Operate/Control



# Validation Example – FRP1 Sensible



# FRP2 DAQ Hardware

- 1 Master Cabinet
- 4 Peripheral Cabinets
- 256 Thermistor Channels
- 256 Single Ended Voltage Channels
- 100 Thermocouple Channels
- 64 Frequency input or 5V control Channels



# FRP2 Installed Sensors

- 35 Temp/RH Probes
- 6 Refrigerant Side Immersion Thermistors
- 6 Refrigerant Side Pressure Transducers
- 2 Refrigerant Mass Flow Sensors
- 1 Natural Gas Mass Flowmeters
- 2 Airflow Measurement Stations
- 16 HVAC Power Measurements (Wattnode and CTs)
- 21 General Building Power Measurements (Wattnode and CTs)

# FRP 2 Sensors



**Refrigerant mass flow**



**Natural gas flow**




**Electrical power**



**Refrigerant temperature and pressure**




**Airflow**



**Air temperature/relative humidity**

# Layout of Measurements



# Technical Specs of Measurement

Sensors	Measurement	Accuracy
Campbell Sci HC2S3-L	Temperature/relative humidity (RH)	$\pm 0.1^{\circ}\text{C}$ and $\pm 0.1\%$ RH @ $23^{\circ}\text{C}$
Continental Controls WNB-3D-240P	Power	$\pm 0.5\%$ of reading
Omega 44031 immersion thermistor probes	Temperature	@ 0 to $70^{\circ}\text{C}$ is $\pm 0.1^{\circ}\text{C}$
Omega PX409-750-A5V pressure transducers	Pressure	$\pm 0.08\%$ best straight line maximum
Sierra BT620 thermal flowmeter	Gas flow	$\pm 1\%$ of full scale (actual gas calibration) and $\pm 1\%$ of full scale/ $\pm 3\%$ of reading (correlation); repeatability $\pm 0.2\%$ of full scale
Air monitor fan evaluators paired to DPT2500 Plus transmitters	Air flow	DTP2500— $0.25\%$ of natural span, including hysteresis, deadband, nonlinearity, and nonrepeatability; fan evaluator— $\pm 2\%$



# Evaluation Metrics/Validation Parameters

#	Parameters	Sub-parameters	Unit	Note
1 - 3	RTU energy use	DX cooling	Wh	2 stage cooling coil
		Evaporative fan	Wh	Main supply fan with VFD
		VAV box (electric reheat)	Wh	Individual electric reheating for each VAV box
4	RTU discharge temperature		F	Fixed discharge temperature for RTU
5	RTU return air temperature		F	Mixed return air temperature from 10 zones
6	RTU supply air flow		CFM	
7	Supply air flow for each zone		CFM	TBD—no sensors are available for zone-level air flow measurement yet
8	Room temperature for each zone		F	10 measurement points. Temperature sensor is located in the middle of each zone
9	Room RH for each zone		%	10 measurement points. RH sensor is located in the middle of each zone



# Develop and calibrate FRP model

## *As-Built model*

- Use previously developed model with RTU
- Modify the model with recent envelop retrofit and system changes

## *Calibrate the model*

- Use existing measured data : Summer 2015-Spring 2016
- Run FRP with 3 full days without HVAC & no internal gains, no exhaust (Summer FY 16)
- Run FRP with 3 full days with HVAC without setback and no internal gains, no exhaust (Summer FY 16)
- Run FRP with 3 full days without HVAC & no internal gains, no exhaust (Winter FY 17)
- Run FRP with 3 full days with HVAC without setback and no internal gains, no exhaust (Winter FY 17)



# Multi-Year Plan

- Outlines current multi-year plan
  - 19 pages

## Validation Study for EnergyPlus Multi-Zone HVAC System using ORNL's Flexible Research Platform



Piljae Im  
Mahabir Bhandari  
Joshua New

**Date: June 2016**

# Experimental Plan : Cooling Equipment Validation

## *ASHRAE 140 Cooling equipment cases*

- Objective is to verify envelope and mechanical properties under idealized test conditions
- Building/system specification not consistent with FRP
- E.g., envelope R-value  $\sim 567 \text{ h}\cdot\text{ft}^2\cdot^\circ\text{F}/\text{Btu}$ , and the infiltration rate is zero, which cannot be realized in real buildings such as FRP.
- Reviewed CE100, CE110, CE120, CE130, CE150, CE160, and CE165
- Suggested a set of test conditions



# Experimental Plan : Cooling Equipment Validation

**Test period:** One week in summer for each test case, 1 day for warm up and 3 days with HVAC operation

## *Test 1: Cooling Baseline*

- No occupancy emulation
- All internal lights are turned off
- Fixed discharge temperature of 55°F and no Outdoor air ventilation or exhaust air
- No humidity control and no heating
- Fixed zone set point temp of 72°F

# Experimental Plan : Cooling Equipment Validation

## *Test 2: Reduced outdoor dry-bulb temperature*

- Same as **Test 1** (i.e., tested when colder than Test 1)

## *Test 3: Cooling with increased thermostat set point*

- Increase zone set point to: 26.7°C (80°F)
- Rest of the conditions same as in **Test 1**

## *Test 4: Cooling with low part-load ratio*

- Modulate part load ratio – use internal heaters
- Rest of the conditions same as in **Test 1**

# Experimental Plan : Cooling Equipment Validation

## *Test 5: Latent load at high sensible heat ratio*

- Use heaters and humidifiers
- Rest of the conditions same as in **Test 1**

## *Test 6: Increased thermostat setpoint at high sensible heat ratio*

- Increase zone set point to: 26.7°C (80°F)
- Rest of the conditions same as in **Test 5**

## *Test 7: Variation of thermostat setpoint at high sensible heat ratio*

- Zone set point includes setup/setback:
  - through 6 a.m.: 88°F
  - 6 a.m. through 6 p.m.: 75°F
  - 6 p.m. through 12 a.m.: 88°F
- Rest of the conditions same as in **Test 6**

# Experimental Plan : Heating Equipment Validation

## *ASHRAE 140 Heating equipment cases*

- 140 test cases include a fuel fired furnace, but FRP is equipped with electric reheat only.
- Reviewed HE100, HE210, and HE220
- Suggested only two test conditions



# Experimental Plan : Heating Equipment Validation

## *ASHRAE 140 Heating equipment cases*

### *Test 8: Heating Baseline*

- No occupancy emulation
- All internal lights are turned off
- Fixed discharge temperature of 55°F and no OA or EA (VAV terminal reheat, some rooms need cooling even during heating season; from RTU to VAV boxes, damper modulating)
- No humidity control
- Fixed zone set point temp of 68°F

### *Test 9: Heating with setback thermostat*

- Zone setpoint includes setup/setback:
  - through 6 a.m.: 59°F
  - 6 a.m. through 6 p.m. 69°F
  - 6 p.m. through 12 a.m.: 59°F
- Rest of the conditions same as in **Test 6**

# Discussion

Joshua New, Ph.D.  
newjr@ornl.gov

